

Pump Controller Guide

Model Aquila PX-4 | Revision 1.0

Overview

The Aquila PX-4 coordinates a variable-speed pump with dry-run protection.

Record the verified motor rating and installation identifier before commissioning.

WARNING: condition=power is connected; consequence=electric shock; avoidance=isolate power

Commissioning procedure

1. Isolate incoming power.
2. Verify terminal torque.
3. Run the low-speed test.

Parameter	Default	Allowed range
Ramp time	8 s	2-60 s
Stop delay	3 s	0-20 s